

Kalida Elementary School Project – Gym doors and sidelights in lobby area

Project: Materials and labor to install three (3) double doors with transoms, eight (8) gym door sidelights and eight (8) hall sidelights.

Description of Entrance Materials

Door/sidelight Frame Type	Storefront Framing – 2” x 4 ½ ” 5” sides and tops with 10” high bottoms
Arrangement	Half Panel / Half Glass on doors
Glass Type	1” clear tempered/insulated safety glass lo “E”
Panel Type	1” Fluted Aluminum Panel (FAP) or textured aluminum skinned insulated panel – standard color “Clear anodized”
Door Seal	Deep pile weather-stripped door stops, weather-stripping doors and sweep strip at threshold
Hardware	LCN #4040XP H-Cush Closer with Hold Open or similar comparable quality Panic Hardware Rodon Continuous Hinge Pull Handle Remove/reinstall existing security/motion sensor magnet lock
Key Cylinder	Construction cylinder
Centerpost	2” – non removable
Frame Finish	Class 1 clear anodized
Warranty	Entrance: 5 year from date of installation Installation: 1 year from date of installation

The estimated cost of this project is \$35,000

Please contact Superintendent Karl Lammers (419-532-3534) for an onsite project inspection.